

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

2

API NUMBER 15-077-20619-0000

LEASE NAME Smith

WELL NUMBER 2

1980 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 2 TWP. 31 RGE. 7W (E or W)

COUNTY Harper

Date Well Completed 9-19-80

Plugging Commenced 4-16-87

Plugging Completed 4-18-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gressel Corporation

ADDRESS P.O. Box 322 Haysville, Kansas 67060

PHONE#(316) 773-1248 OPERATORS LICENSE NO. 5822

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Wichita

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4344 Bottom 4360 T.D. 4390

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>K.C.</u>	<u>Water</u>	<u>3822</u>	<u>4065</u>	<u>8 5/8</u>	<u>257</u>	<u>None</u>
<u>Mississippi</u>	<u>Oil and Water</u>	<u>4344</u>	<u>4360</u>	<u>4 1/2</u>	<u>4389</u>	<u>2,964</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

4390 to 3143 tubing and rods stuck hole full of rotary mud= Sand back to 3100 cement dumped to 3043. Ripped casing off at 2964 mud to 350 rock bridge 350 to 325 filled with reaymix to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corp License No. 5822

Address P.O. Box 322, Haysville, Kansas 67060

STATE OF Kansas COUNTY OF Sedgewick, ss.

Gressel Corporation (Dewey Gressel) (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dewey Gressel

(Address) Po Box 322 Haysville Ks



SUBSCRIBED AND SWORN TO before me this 22 day of April, 1987

L. C. Deane Notary Public

My Commission Expires: 6/12/89

RECEIVED 1987
STATE CORPORATION COMMISSION
APR 23 1987
4-23-87
Form CP-4
CONSERVATION DIVISION
Wichita, Kansas
Revised 07-86

15-077-20619-0000

W. PAT SIMMONS

GEOLOGIST

REGISTERED

DRILLING PROSPECTS -- OIL & GAS INVESTIGATIONS -- WELL SUPERVISION -- WELL COMPLETIONS

5252 NORTH BROADWAY • WICHITA, KANSAS 67210 • 316 838-3761

September 23, 1980

GEOLOGIC REPORT

Indian Wells Oil Company
Smith # 2
C NE SW Section 2-31S-7W
Harper County, Kansas

Elevation 1595 RB

Commenced: 9/11/80

Completed: 9/19/80

Development Well

I. P. - Pending

Casing Record

8 5/8" @ 257'/200 sax.

4 1/2" @ 4389'/Halliburton

SUMMARY OF FORMATIONS

Heebner	3285 (-1690)
Douglas	3385 (-1790)
Stalnaker	3683 (-2088)
Kansas City	3822 (-2227)
Base of Kansas City	4065 (-2460)
Conglomerate	4331 (-2736)
Mississippian	4344 (-2749)
"Pay Zone"	4352 (-2757)
Rotary Total Depth	4390 (-2795)

CORES: None

ELECTRIC LOGS: None

DRILL STEM TESTS: None

SUMMARY OF POROUS ZONES & OIL SHOWS

Conglomerate: (4331-4344) Composed of shales; red, yellow, gray and green with some sand clusters. Some red and yellow cherts with no shows.

Mississippian: (4344-4352) Composed of cherts white to yellow, sharp and fresh. No shows.

(4352-4360) Cherts leached and tripolitic with good apparent porosity carrying a good odor. Good show of free oil and good florescence. Estimate Commercial.

RECOMMENDATIONS

This well ran structurally favorable as compared with other wells in the immediate area. It was a few feet lower than the Williams # 1, the north offset, and a few feet higher than the Smith # 1, the southwest offset.

Good shows of oil and gas were encountered in the "Pay Zone" section in this well from 4352 to 4360 feet and were considered to be of Commercial value.

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1987

4-15-87

Wichita, Kansas