


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

HARPER County, Sec. 13 Twp. 31S Rge. 2W (X) (W)
C SW SE

Location as "NE/CNW'SW" or footage from lines _____
Lease Owner Sierra Petroleum Co., Inc.
Lease Name BROWNING Well No. 1
Office Address 1015 Wichita Plaza Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed June 17, 19 64
Application for plugging filed June 17, 19 64
Application for plugging approved June 17, 19 64
Plugging commenced June 17, 19 64
Plugging completed June 17, 19 64
Reason for abandonment of well or producing formation DRY HOLE

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Herman E. Justus, Nickerson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4824 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Sand, Shale & Red Bed</u>	<u>Surface Casing</u>	<u>-0-</u>	<u>198'</u>	<u>8-5/8"</u>	<u>198'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED HOLE: Filled hole with mud from T.D. to 200'. Bridge & plug @ 200' & 25 sz. cement. Filled with mud to 40'. Bridge & plug @ 40' & 10 sz. cement. 2 sz. cement in rat hole.
Job completed @ 3:15 p.m. 6-17-64.

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1964
6-22-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 1015 Wichita Plaza Building, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF RUSSELL, ss.
S. P. Hall, Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. S. P. Hall

(Signature) S. P. Hall, Superintendent

Box 232, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of June, 1964.

My commission expires 10-17-67

Gray Dutz
Notary Public.

SIERRA PETROLEUM CO., INC. - Operator

T. D.: 4824'
Elev.: 1591' K.B.

BROWNING #1
C SW SE
Sec. 13-31S-8W
Harper County, Kansas

Commenced: 6-5-64
Completed: 6-17-64

Casing:

8-5/8" Set at 198'

Cement:

with 165 ex. G.L.3

FORMATION

DEPTH

Sand & Shale
Red Bed
Red Bed & Shale
Shale & Shells
Salt
Shale & Lime
Shale & Shells
Shale & Lime
Lime
Mississippi Chat
Chert
Lime
Lime & Shale
Lime
Lime & Sand
Sand & Lime

120
198
950
1175
1230
2155
2655
3895
4418
4430
4495
4650
4690
4809
4823
4824

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1964

6-22-64

CONSERVATION DIVISION
Wichita, Kansas

TOPS

Hoebner
Toronto
Stalmaker
Base Stalmaker
Kansas City
Mermeton
Cherakee
Mississippi

3389
3417
3712
3721
3883
4178
4283
4418

STATE OF KANSAS)
COUNTY OF RUSSELL) ss:

I hereby certify that the above information is true and correct to the best of my knowledge.

S. P. Hall
Superintendent

Subscribed and sworn to before me this 20th day of June, 1964.

Leroy D. Dwyer
Notary Public

My commission expires: 10-17-67