

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84
RECEIVED
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM
(File One Copy)

DEC 14 1988

12-14-88

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15-077-20,581-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR McCoy Petroleum Corporation OPERATORS LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500 PHONE # (316) 265-9697

LEASE (FARM) Cramer "B" WELL NO. 1 WELL LOCATION NW NW SW COUNTY Harper

SEC. 15 TWP. 31 RGE. 8 (E) or (W) TOTAL DEPTH 4386 PLUG BACK TO _____

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 280 CEMENTED WITH 250 SACKS

CASING SIZE 4-1/2" SET AT 4375' CEMENTED WITH 125 SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP in 4-1/2" casing at approximately 4310' Place 3 sacks cement on top of CIBP . Cut off and pull approx. 3300' of 4-1/2"

casing. Plug 8-5/8" surface casing with pump truck using 5 sx hulls, 30sx gel & 110 sx 60-40 Poz.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN October 25, 1988 8.00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE # (316) 265-9697

ADDRESS 1819 Eleanor, Kingman, KS 67068

PLUGGING CONTRACTOR Hayes Well Service LICENSE NO. 5429

ADDRESS Attica, Kansas PHONE # (316) 254-7204

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: John Roy McCoy
(Operator or Agent)

DATE: 12-13-88