# STATE OF KANSAS STATE CORPORATION COMMISSION CONSERVATION DIVISION 200 Colorado Derby Building Wichita, Kansas 67202

## WELL PLUGGING APPLICATION FORM (File One Copy)


API NUMBER 15-077-20.544-000 (of this well) (This must be listed; if no API# was issued, please note drilling completion date.)	
LEASE OPERATOR McCoy Petroleum Corporation	OPERATORS LICENSE NO. 5003
ADDRESS 110 South Main, Suite 500, Wichita, KS 67202 PHONE # (316 ) 265-9697	
LEASE (FARM) Leeper "D" WELL NO. 1 WELL LOCATION C NW NE COUNTY Harper	
SEC. 15 TWP. 31 RGE. 8 Or (W) TOTAL	DEPTH 4429 PLUG BACK TD 4429
Check One:	
OIL WELL X GAS WELL D&A SWD	or INJ WELL DOCKET NO
SURFACE CASING SIZE 8-5/8" SET AT 24	81 CEMENTED WITH 250 SACKS
Production CASING SIZE 4-1/2" SET AT 4417	CEMENTED WITH 125 SACKS
PERFORATED AT Open Hole 4417-4429'	
CONDITION OF WELL: GOOD X POOR C	CASING LEAK JUNK IN HOLE
OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set 4-1/2" Arrow Bridge Plug @ 4400'+-	
in 4-1/2" casing, Pull 4-1/2" casing above approximately 3750'. Plug 8-5/8" surface casing	
using Halliburton cement Truck as follows: See	
(If additional space is n	needed use back of form)
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUI	RED? Yes IS ACO-1 FILED? Yes
DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 4-23-	86 8:00 a.m.
PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE REGULATIONS OF THE STATE CORPORATION COMMISSION.	NOTE WITH K.S.A. 55-101 et seg AND THE RULES AND
NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE I	IN CHARGE OF PLUGGING OPERATIONS:
Daryl Hanson	PHONE # (316) 532-5452
ADDRESS Kingman Kansas	STATE CORPOGATION COMMISSION
PLUGGING CONTRACTOR Hayes Well Service	LICENSE NO. 5429 APR 21 1988
ADDRESS Attica, Kansas	PHONE # 316) 254-7204 Wichita Van
PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT	SIGNED: John Loge Malon (Operator or Agent)
( <u>a</u> )	DATE: 4-18-86

- 1. Attach a wireline to Halliburton LA-11 cementing plug.
- 2. Push the plug to a depth of 200' with tubing. Tie the wireline at the surface.
- 3. Push one sack of cottonseed hulls (in the sack) to a depth just above the LA-11 Plug.
- 4. Load the hole with water. Spot 25 sacks of densified 50-50 Pozmix Cement (no gel) containing 3% calcium chloride, on top of cottonseed hulls.
- 5. Pull tubing. Watch fluid level.
- 6. Wait about 2 hours. Check fluid level.
- 7. If fluid is static, spot 25 sacks of 50-50 Pozmix cement (no gel) with 3% calcium chloride to the surface.

State of Kansas

JOHN CARLIN Governor
MICHAEL LENNEN Chairman
MAHGALEE WRIGHT Commissioner
KEITH R HENLEY Commissioner
JUDITH A. McCONNELL
BRIAN J MOLINE Executive Secretary
General Counsel





## State Corporation Commission

#### CONSERVATION DIVISION

(OII, Gas and Water) 200 Colorado Derby Building 202 West 1st Street WICHITA, KANSAS 67202-1286

Tras RumuE

july 2 1 1936

April 21, 1986

**EXPIRES** 

WELL PLUGGING NOTICE

Leeper "D" #1 C NW NE Sec. 15-31S-8W Harper County

McCoy Petroleum Corporation 110 South Main, Ste. 500 Wichita, KS 67202

#### Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

William R. Briper

Please contact the district office to review your suggested method of plugging

DIST. #2 3244 E. Douglas Wichita, KS 67208 316-651-5506

five days prior to plugging the well (KAR-82-3-113).