

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

15-051-06393-0000

API NUMBER D&C 11-14-60

(of this well) 6/85

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Gulf Oil Corporation OPERATORS LICENSE NO. 5816  
ADDRESS P.O. Box 12116, Oklahoma City, OK 73157 PHONE # (405) 949-7000  
LEASE (FARM) Leinmiller "B" WELL NO. 2 WELL LOCATION 2310 FSL COUNTY Ellis  
SEC. 2 TWP. 12S RGE. 19 (X) or (W) TOTAL DEPTH 4215' PLUG BACK TO Open Hole

Check One:

OIL WELL ☐ GAS WELL ☐ D & A ☐ ~~S&W~~ INJ WELL ☒ DOCKET NO. 65,925-C  
SURFACE CASING SIZE 8 5/8" SET AT 245' CEMENTED WITH 175 SACKS  
CASING SIZE 5 1/2" SET AT 3768' CEMENTED WITH 200 SACKS  
PERFORATED AT None - Open Hole 3768-4215'

CONDITION OF WELL: GOOD ☒ POOR ☐ CASING LEAK ☐ JUNK IN HOLE ☐

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Shown on back of form.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? See attached IS ACO-1 FILED? No Record  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As Soon As Possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. C. T. Oglesby PHONE # (316) 265-3169

ADDRESS P.O. Box 2063, Wichita, KS 67201

PLUGGING CONTRACTOR DC&DS Well Service LICENSE NO. 9260

ADDRESS 526 East 5th St., Russell, KS 67665 PHONE # (913) 483-6133

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED:

Dorretta Moore  
(Operator or Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1985

DATE:

April 16, 1985

NOTE: Mail P&A Approval To: CONSERVATION DIVISION  
Dorretta Moore  
c/o Gulf Oil Corporation, P.O. Box 12116, Okla. City, OK 73157  
Mail P&A Invoice To: Gulf Oil Corporation, P.O. Box 2063, Wichita, KS 67201

(b)

Linn Miller B#2

Sec. 2 - 125 - 19W

Ellis County, Ks.

Procedure to P+A

- (1) MIRR P.H. Haset phr. Circ well w/ 100 lbs mud
- (2) MIRR Wireline. RIH w/ gauge ring to  $\pm 3760'$ .  
RIH + set CIBP at  $\pm 3750'$ . Dump 10' cmt. on  
CIBP. RDM9 Wireline.
- (3) MIRR Cq. pullers. Cut cq off at free point.  
Circ. well full of 9" ppg mud.
- (4) POH w/ cq. to 300'. Circ. well full w/  
150 sks. CH cmt. POH w/ cq. Top off cmt. well
- (5) Check TOC.
- (6) Cut cq off 6' below G.L. Well cap. ID  
well. Restore surface.

Jarvis Marshall  
11-6-84

Noted gmb  
Approved \_\_\_\_\_



N. CARLIN  
HAEL LENNEN  
GALE WRIGHT  
H. R. HENLEY  
TH. A. McCONNELL  
W. J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

## THIS NOTICE

JUL 18 1985

April 18, 1985  
WELL PLUGGING NOTICE

EXPIRES

Leinmiller "B" #2  
2310' FSL 990' FWL  
Sec. 2-12S-19W  
Ellis County

Gulf Oil Corp.  
P. O. Box 12116  
Oklahoma City, OK 73157

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "William R. Bryson".

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to  
DIST. #6 1014 Cody Hays, KS 67601 913-628-1200  
five days prior to plugging the well (KAR-82-3-113).