


15-077-10078-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 19 Twp. 31S Rge. 8W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW/SW/SW

Lease Owner S.A. Berwick Drilling Co.

Lease Name Darnes Well No. C #1

Office Address 1105 Williams Street, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19

Plugging commenced 11-30-56

Plugging completed 12-6-56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Mr. M.A. Rives Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4380' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3837'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into TD 4380'.
Plugging started 11-30-56. Finished 12-6-56.
Plugged off bottom with sand and dumped 5 sacks cement. Shot 5 1/2" casing at 3837'. Pulled pipe out of hole and plugged well with heavy mud to 200' and set permanent rock bridge. Dumped 20 sacks cement. Filled hole with mud to 35' and set rock bridge. Mixed 10 sacks cement for cap on well.

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1956
12-12-56
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of December, 1956

My commission expires April 8, 1957
Notary Public.

PLUGGING
FILE SEC 19 T. 31 R. 8W
BOOK PAGE 119 LINE 35

S.A. BERWICK DRILLING COMPANY

1105 Williams
Great Bend, Kansas

Darnes C #1

Total Depth: 4380'
Commenced R.D.: 9-28-55
Completed R.D.: 10-13-55

SW SW SW Sec 19-31S-8W
Harper County, Kansas
Elevation:
Initial Prod:
Contractor: S.A. Berwick
Drilling Co.

Strata	Depth
Sand	0 - 20'
Red Rock	20 - 165'
Shale	165 - 200'
Shale and Shells	200 - 280'
Anhydrite	280 - 1152'
Shale and Shells	1152 - 1325'
Lime	1325 - 2050'
Lime and Shale	2050 - 3653'
Sandy Lime	3653 - 3670'
Lime	3670 - 3815'
Lime and Shale	3815 - 3973'
Lime	3973 - 4315'
Lime and Shale	4315 - 4365'
Lime	4365 - 4380'

I hereby certify the above a true and correct log of said well as reflected by the daily drilling report.

S.A. BERWICK DRILLING COMPANY

By S.A. Berwick
S.A. Berwick Owner

Signed and sworn to in my presence this 16 of November, 1955 by S.A. Berwick, owner of the S.A. Berwick Drilling Company.

John A. [Signature]
Notary Public

My Commission Expires: 4-11-59

PLUGGING
FILE SEC 19 T 31 R 8W
BOOK PAGE 119 L 35

RECEIVED
STATE CORPORATION COMMISSION
NO. 11-27-56
CONSERVATION DIVISION
Wichita, Kansas