

15-077-00131-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Affidavit Required  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Harper

County. Sec. 19 Twp. 31 Rge. 8 (E) (W)

Location as "NE/CNW&SW" or footage from lines SW NW NE

Lease Owner National Cooperative Refinery Association

Lease Name Washbon Well No. 1

Office Address 305 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed September 18, 1954

Application for plugging filed July 10, 1956

Application for plugging approved July 11, 1956


Plugging commenced July 24, 1956

Plugging completed July 30, 1956

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production July 12, 1956

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4476 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT	
				8 5/8"	168'	None	
				5 1/2"	4467'	3954'	
		Casing perforated at 4385' and hole plugged back to 4445'.					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed the packer from 1300' to 4440' and filled the hole with sand to 4375'.

Ran 5 sacks of cement on top of sand. Pulled casing up to 1800' and circulated the hole with 60 sacks of jell mud. Bailed mud to 210', set a 10' rock bridge to 200' and filled the hole to top of the surface casing with 75 sacks of cement.

Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. R. Sears (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)

305 Rule Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of August, 1956

Neil McComb

Notary Public.

My commission expires November 26, 1956.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 7 1956  
8-7-56  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 19 T. 31 R. 8W  
BOOK PAGE 79 LINE 5


15-077-08131-0000  
**KANSAS GEOLOGICAL SOCIETY**  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **M. B. Armer**  
 FARM **Washbon** NO. **1**

SEC. **19** T. **31S** R. **8W**  
 LOC. **SW NW NE**

TOTAL DEPTH **4476**  
 COMM. **8/18/54** COMP. **9/2/54**  
 SHOT OR TREATED  
 CONTRACTOR **M. B. Armer**  
 ISSUED

COUNTY **Harper**  
 KANSAS



CASING

20	10	
15	8	168'
12	6	
13	5	4475'

ELEVATION **1619 K.B.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- Sand 75
- Red Bed 550
- Shale & Shells 670
- Sand 760
- Shale & Shells 925
- Anhydrite 960
- Shale & Shells 1130
- Lime & Shale 1630
- Broken Lime 1745
- Shale & Lime 2000
- Shale - Streaks of Lime 2200
- Lime & Shale 2557
- Broken Lime 2740
- Shale & Lime 3341
- Lime 3790
- Lime & Shale 3905
- Lime 3988
- Shale & Lime 4076
- Lime 4220
- Lime & Shale 4208
- Lime 4254
- Shale & Lime 4349
- Lime 4382
- Chat 4476

FORMATION TOPS (As measured from K.B.)

MISSISSIPPI 4382

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

By *[Signature]*

STATE OF KANSAS  
 COUNTY OF SEDGWICK  
 SS: 7-11-56

Subscribed and sworn to before me, a notary public, in and for said County and State this 7th day of September, 1954.

*[Signature]*  
 Notary Public

My Commission expires February 13, 1956.

**PLUGGING**  
 FILE SEC. 19 T. 31 R. 8W  
 BOOK PAGE 79 LINE 5