


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County. Sec. 19 Twp. 31 Rge. 8 (E) (W) X
Location as "NE/CNW4SW4" or footage from lines SE SW SE
Lease Owner Mull Drilling Company, Inc.
Lease Name Washborn Well No. A-1
Office Address 1625 Wichita Plaza Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 7-15-66 19____
Application for plugging approved 7-16-66 19____
Plugging commenced 8-1-66 19____
Plugging completed 8-5-66 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1112 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5.8	<u>260</u>	None
				5 1.2	None <u>4412</u>	3335

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Cleaned out cellar.

Sanded to 4375'. Dumped 5 sacks of cement. Working pipe.

Working pipe. Shot pipe at 3600' - 3500' - 3400' and 3310'. Pulling pipe.

Pulling pipe. Plugging well. Build rock bridge at 240'. Dumped 35 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

Cleaned and doped threads.

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1966

8-11-66

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10 day of August, 19 66

My commission expires May 27, 1969

[Signature]
Notary Public.

ROTARY DRILLERS LOG

COMPANY : Mull Drilling Co., Inc. Et Al
Wichita, Kansas

ROTARY DRILLING COMMENCED:
6-28-58

CONTRACTOR : Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED:
7-12-58

CASING RECORD: Set 8 5/8" @ 200' w/150
sax cement
Set 5 1/2" @ 4412 w/150
sax posmix

LOCATION: WASHBON #1
SE SW SE 19-31S-8W
Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

700'	Red Bed
1380'	Shale & Shell
1568'	Lime
1705'	Lime w/Shale
1777'	Lime
2095'	Lime & Shale
2695'	Broken Lime & Shale
3107'	Lime & Shale
3622'	Sandy Lime & Shale
4000'	Lime w/Shale
4298'	Lime
4392'	Lime w/Shale
4412'	Mississippi - Total Depth

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1966
8-19-66
CONSERVATION DIVISION
Wichita, Kansas


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

by *Joseph S. Brungardt, Jr.*
Joseph S. Brungardt, Jr., Treas.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 16th day of July, 1958.



Mador N. Miller
Notary Public

My Commission Expires: February 24, 1960