

15-077-10141-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Harper County, Sec. 15 Twp. 31 Rge. 8 (E) W(W)
Location as "NE/CNWSW" or footage from lines NW SE NW
Lease Owner Mack Oil Company
Lease Name Stephens Well No. # 1
Office Address P. O. Box 400 ; Duncan, Okla.
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed November 1973
Application for plugging approved November 1973
Plugging commenced December 14 1973
Plugging completed December 24 1973
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	166	None
				5 1/2"	4481	2787

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

December 14, 1973 Plugged off bottom. Dumped sand to 4300'.
Mixed and dumped 5 sx of cement.

December 24, 1973 Plugged off top. Set 10' rock bridge at
320'. Filled 8 5/8" surface casing from 320'
to base of cellar with 3000 lb. P.S.I. ready-
mix concrete.

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1974
1-16-74
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RISS CASING PULLING, INC.
Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF OKLAHOMA, COUNTY OF STEPBENS, ss.
CARI A BENTLEY (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl A Bentley
P. O. Box 400, Duncan, Okla. 73533
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of January, 1974

Ralphine Bentley
Notary Public.

My commission expires 3-24-75

15-077-10141-0000

Purchased by Mack Oil Co.
3-1-65

SHOLOM DRILLING COMPANY, INC.
6045 Pine Tree Drive
Miami Beach, Florida 33140

COMPANY: Robinowitz Oil Company & Petroleum Operating Co.
FARM: Stephens
LOCATION: NW SE NW Sec 15 T31S R8W, Harper County, Kansas
ROTARY DRILLING CONTRACTOR: Sholom Drilling Company, Inc.

COMMENCED: 2/8/64
COMPLETED: 2/21/64 to RTD
I. P:

ELEVATION: 1615' KB
ROTARY T. D.: 4485'

CASING RECORD:
8 5/8" @ 166' w/150 sax
5 1/2" @ 4481' w/130 sax

L O G

0 - 90 Clay and sand
90 - 166 Shale
166 - 1278 Shale and red bed
1278 - 1335 Anhydrite
1335 - 1500 Shale
1500 - 3590 Lime and shale
3590 - 3893 Lime
3893 - 3935 Lime and shale
3935 - 4389 Lime
4389 - 4404 Chert

Mississippi 4389'

DST 4391 - 4404 20' mud, 120' oil
cut mud, 210 Very heavy oil cut
mud, 120' muddy oil, 30' water.
BHP 1480, FBHP 1360,
Flow 60-80

DST 4406-4424 Rec. 30' oil cut mud,
370' heavy oil cut mud, 60' water.
BHP 1300#, Flow 0-120#

Schlumberger-Gamma Ray, Laterlog, Sonic
run at T. D.

STATE OF FLORIDA)
)ss
COUNTY OF DADE)

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1973
11-21-73
CONSERVATION DIVISION
Wichita, Kansas

I, Joseph Teichman, President of Sholom Drilling Company, Inc.,
a corporation of the State of Oklahoma, domesticated in the State of Kansas,
being first duly sworn under oath, says: That I have knowledge of the facts,
statements and matters herein contained of the above described well as filed,
and that the same are true and correct.


Joseph Teichman

Subscribed and sworn to before me this 28th day of February, 1964.


Notary Public

NOTARY PUBLIC STATE of FLORIDA at LARGE
MY COMMISSION EXPIRES JAN. 26, 1968
BONDED THROUGH FRED W. BIEGELHORST

My Commission expires: _____