


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Harper County. Sec. 16 Twp. 31 Rge. 6 (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NW, NW, NW.
Lease Owner Theodore Gore
Lease Name Bush Well No. 1
Office Address 400 Brown Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 12, 1957 19 57
Application for plugging filed June 12, 19 57
Application for plugging approved June 12, 1957 19 57
Plugging commenced June 12, 19 57
Plugging completed June 12, 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives
Producing formation 9 Depth to top none Bottom none Total Depth of Well 4738 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					240ft 8 5/8	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with heavy rotary mud. from T.D. to 2240 Plug set at 240 and 20 sacks of cement on top of plug. Mud on top of cement plug set at 40 10 sacks of cement on top of plug surface pipe cut off three feet below ground level.

RECEIVED

6-13-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mull Drilling Contractor Inc.
Address 6405 E. Kellogg Wichita, Kansas

STATE OF Kansas COUNTY OF Harper ss.
O. C. Arnott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. C. Arnott
Atties Kan (Address)

SUBSCRIBED AND SWORN TO before me this 12 day of June 19 57
Therese M. Haire Notary Public.

My commission expires Jan. 7, 1961

PLUGGING
FILE SEC 16 T. 31 R. 6W
BOOK PAGE 20 LINE 14

ROTARY DRILLERS LOG

COMPANY : Ted Gore
 Wichita, Kansas

ROTARY DRILLING COMMENCED: 5-27-57

CONTRACTOR : Mull Drilling Company, Inc.
 Wichita, Kansas

ROTARY DRILLING COMPLETED: 6-12-57

CASING RECORD : Set 8 5/8" @ 240' cemented
 with 150 sacks cement.

LOCATION: BUSH #1
 NW NW NW of Sec. 16-31S-6W
 Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Clay	20
Red Rock	240
Red Bed	645
Shale	1100
Lime & Shale	3779
Lime	3995
Lime & Shale	4298
Chat	4574
Shale	4696
Simpson	4738' R.T.D.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.


MULL DRILLING COMPANY, INC.

BY *Joseph B. Brungardt, Jr.*
 JOSEPH B. BRUNGARDT, JR.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 14th day of June, 1957.

Madse N. Miller
 NOTARY PUBLIC



COMMISSION EXPIRES: FEBRUARY 24, 1960.

RECEIVED
 STATE CORPORATION COMMISSION

JUN 19 1957
 6-19-57
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 16 T. 31 R. 6W
 BOOK PAGE 20 LINE 14