

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Joslin
 WELL NUMBER 1-11
4620 Ft. from S Section Line
2970 Ft. from E Section Line
 SEC. 11 TWP. 31 SRGE. 6W (E) or (W)
 COUNTY Harper
 Date Well Completed 11-18-85
 Plugging Commenced 9-24-92
 Plugging Completed 9-28-92

LEASE OPERATOR MTM Petroleum Inc.
 ADDRESS 113 Main St. Spivey, Ks. 67142
 PHONE#(316) 532-5178 OPERATORS LICENSE NO. _____

Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-22-92 (date)
 by John Sanders #2 (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes
 Producing Formation miss. Depth to Top 4200 Bottom 4365 T.O. 4710

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	water	0	373	8 5/8	373	none
		0	4730	4 1/2	4729	3000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
Sand back to 4125 spot 4 sx cement, shoot off pipe and lay down to 990 ft, pump 35 sx plug, pull to 600 ft and spot 35 sx plug, pull to 425 ft and circulate to surface with cement.

Name of Plugging Contractor VAL Energy, Inc. License No. 5822
 Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MTM Petroleum Inc.
 STATE OF Kansas COUNTY OF Sedgwick, ss. OCT 6 1992

K Todd Allam (Employee of Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.
 (Signature) [Signature]

(Address) Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 92

Mary D. Stearns
 Notary Public

My Commission Expires:
 USE ONLY ONE SIDE OF EACH FORM

