

API NUMBER 15-077-21169-0000

LEASE NAME E.E. Keller

WELL NUMBER 1

330 Ft. from <sup>N</sup> Section Line

400 Ft. from <sup>W</sup> Section Line

SEC. 31 TWP. 31 RGE. 6 ~~KXXK~~(W)

COUNTY Harper

Date Well Completed N/A

Plugging Commenced 3-24-94

Plugging Completed 3-28-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

*Copy*

LEASE OPERATOR Bryce Hayes Oil & Gas

ADDRESS P.O. Box 108, Attica, KS 67009

PHONE# (316) 254-7204 OPERATORS LICENSE NO. 5429

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-24-94 (date)

by Dave (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	307	None
				4 1/2	4379	3710

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from    feet to    feet each: Pumped 100sx hulls, 20sx cement to 3750, cut casing at 3710; pulled casing, ran tubing to 1150, spotted 35sx cement, pulled tubing to 750, spotted 35sx cement, pulled tubing to 350, circulated cement to surface, 60/40, 6%, pulled tubing 3-29-94 checked cement tops in surface pipe, 198' down. Filled to surface with 3 1/2 yds Ready Mix

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bryce Hayes


STATE OF Kansas COUNTY OF Barber, ss.

Jeff Sletto

(Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jeff Sletto

(Address) Medicine Lodge, KS 67104



RECEIVED SUBSCRIBED AND SWORN TO before me this 29 day of March, 1994

STATE CORPORATION COMMISSION

APR 01 1994

4-1-94

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires: Aug. 17, 1994

Glenda Morrison  
Notary Public