

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Runnymede
 WELL NUMBER 1-2
330 Ft. from S Section Line
3630 Ft. from E Section Line
 SEC. 24 TWP. 31 RGE. 6 (E) or (W)
 COUNTY Harper
 Date Well Completed 4-2-57
 Plugging Commenced 12-16-97
 Plugging Completed 12-17-97

LEASE OPERATOR Mai Oil Operations, Inc.
 ADDRESS P.O. Box 33, Russell, Ks 67665
 PHONE (785) 483-2169 OPERATORS LICENSE NO. 5259

Character of Well _____
 () Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on 12-15-97 (date)
 by _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3600 Bottom 3900 T.D. 4695

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	523	cmt'd
				7"	4694	300.6'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Sanded back parts & bailed 7 SKS cement. Shot pipe @ 3006' pulled to 1080' pumped 50 SKS 60-40 POZ 4% gel. Pulled to 1569' pumped 50 SKS 60-40 POZ 4% gel pulled to 201' circ. cement to surface w/ 110 SKS 60-40 POZ 4% gel pulled pipe out.

Name of Plugging Contractor Quality Well Serv. License No. 31925
 Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mai Oil Operations, Inc.


STATE OF Kansas COUNTY OF Russell, ss.

Allen Bangert (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Allen Bangert
 (Address) _____

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 98

Sherril Underwood
 Notary Public



Commission Expires: 10-30-2000

3-9-98