

API NUMBER 15-077-20,581-0000

LEASE NAME Cramer "B"

WELL NUMBER 1

2290' Ft. from S Section Line

330' Ft. from W Section Line

SEC. 15 TWP. 31 RGE. 8 (E) or (W)

COUNTY Harper

Date Well Completed 7-1-80

Plugging Commenced 10-25-88

Plugging Completed 10-25-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well \_\_\_\_\_

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-24-88 (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippian Depth to Top 4371 Bottom T.D. 4386

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	280	8-5/8"	280'	
		0	4375	4-1/2"	4375'	

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 14 1988  
 12-14-88

NO CONSERVATION DIVISION  
 3310' Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP in 4-1/2" casing at approximately 4310'. Place 3 sacks cement on top of CIBP. Cut off and pull approx. 3300' of 4-1/2" casing. Plug 8-5/8" surface casing with pump truck using 5 sx hulls, 30 sx gel and 110 sx 60-40 Pozmix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

John Roger McCoy

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Roger McCoy

(Address) 110 S. Main, Suite 500

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 88

Deborah Ann Paulus  
 Notary Public

My Commission Expires: January 8, 1992

