

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-21,047-0000

LEASE NAME Cramer "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #2

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 15 TWP. 31S RGE. 8 or (W)

COUNTY Harper

Date Well Completed 12-20-84

Plugging Commenced 2-26-96

Plugging Completed 2-28-96

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress, Wichita, KS 67226-4003

PHONE#(316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve VanGieson (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippian Depth to Top 4379 Bottom 4389 T.D. 4389'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	253'	8-5/8"	253'	
		0	4379'	5-1/2"	4379'	2973'

RECEIVED
KANSAS CORP. COM.
MAR 31 1996
P 11:37

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged and abandon using 60/40 Poz. 4% gel. Set 1st plug @ 1320' w/35sx; 2nd plug set @ 914' w/35 sx; 3rd plug set @ 316' w/105 sx circulate to surface. Plugging complete 2-28-96.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address P. O. Box 781624, Wichita, KS 67278-1624

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.



(Signature) [Signature]

(Address) 3017 N. Cypress
Wichita, KS 67226-4003

SUBSCRIBED AND SWORN TO before me this 19 day of March, 19 96

Krista L. Berblinger

Notary Public

My Commission Expires: October 5, 1999 Krista L. Berblinger