


15-077-0014-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Harper County. Sec. 18 Twp. 31 Rge. 8W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NE NW SE
Lease Owner Prime Drilling Co. & Armer Drilling Co.
Lease Name Darnes Well No. 1
Office Address 1005 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-2-54 19____
Application for plugging filed 9-7-54 19____
Application for plugging approved 19____
Plugging commenced 9-7-54 19____
Plugging completed 9-7-54 19____
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud from 4550' to 160'; Set plug and cemented with 20 sax of cement. Filled hole with extra heavy drilling mud from 160' to 35'; set plug and cemented with 10 sax of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company
Address 1005 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. C. A. Prichard contractor & operator
(employee of owner, contractor or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PRIME DRILLING COMPANY

(Signature) C. A. Prichard
1005 Central Bldg., Wichita, Kansas
President
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of September, 1954.

My commission expires 10-14-57.

J. J. [Signature]
Notary Public.

PLUGGING
FILE SEC 18 T 31 R 8W
BOOK PAGE 61 LINE 38

9-8-54
CONSERVATION
WICHITA

ROTARY DRILLING LOG

OPERATOR: Prime Drilling Company
 Armer Drilling Co., Inc.
 Darnes #1
 NE NW SE Sec. 18-31-8W
 Harper County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 8-17-54
 COMP: 9-2-54

FORMATION

REMARKS

Red Bed & Shale	930
Shale & Shells	1335
Shale & Lime	1500
Lime	2105
Lime & Shale	2260
Lime	3200
Lime & Shale	3385
Lime	3670
Lime & Shale	3965
Lime	4000
Lime & Shale	4395
Lime	4407
Lime & Chert	4425
Lime	4455
Lime & Chert	4515
Lime	4550
Total Depth	4550

Ran 8 joints of 8-5/8" 171' Set @ 169'
 Cemented with 150 sax pozmix 2 CC

We certify that the above log is true
 and correct to the best of our knowledge
 and ability.

PRIME DRILLING COMPANY

By R-R. McNeill

PLUGGING
 WELL SEC 18-31-8W
 BOOK PAGE 41 LINE 38

RECEIVED
 STATE CONSERVATION COM.
 SEP-8
 9-8-54
 CONSERV.
 W.P.