

9-6

4-020052

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-20,231-000
CN2 SE SW /4 SEC. 13, 16 S, 12 W
930 feet from S section line
3300 feet from E section line

Operator license# 06588
Operator: Woodman-Iannitti Oil Co.
Address: P.O. Box 308
Great Bend, Kansas 67530

Lease: Dolechek (OWWO) Well # 12
County: Barton
Well total depth 3450 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8" Inch @ 371 feet

112.13

Aband. oil well __, Gas well __, Input well __, SWD X, D & A __

Plugging contractor: Kelso Casing Pulling, Inc. License# 06050

Address: P.O. Box 347, Chase, Kansas 67524

Company to plug at: Hour: _____ Day: 06 Month: September Year: 1994

Plugging proposal received from: Manny

Company: Kelso Casing Pulling, Inc. Phone: 316 938 2943

Were: 8 1/2" Surface casing set @ 371' w/185 sx cmt; 5 1/2" production casing set @ 3353' w/75 sx cmt; Elevation: 1896; Total Depth: 3450; Plug Back Total Depth: 3353'; Anhydrite Depth: 768';

Order 235 sx 60/40 pozmix cmt, 10% gel, 1/2 flowcel/sx and 300# hulls

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 6:00PM, Day: 06, Month: September, Year: 1994

Actual plugging report: Sanded off bottom to 50' above perfs and plugged w/5 sx cmt. Shot off casing @ 2415'. Pulled to 1600' and pumped 110 sx cmt w/200# hulls. Pulled to 790' and pumped 25 sx cmt w/100# hulls. Pulled to 400' and circulated to surface w/100 sx cmt. Pulled remaining casing and topped off hole. Completion time: 6:00PM.

Remarks: Allied Cementing performed the cement job.
Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X. Elevation: 1896 GL _____

I did observe the plugging.

[Signature]
(agent)
Form CP-2/3

RECEIVED STATE CORPORATION COMMISS

INVOLCED
DATE SEP 27 1994
INV. NO. 41282

SEP 09 1994

STATE CORPORATION COMMISS WICHITA, KANSAS