

3-28

RECEIVED  
KANSAS CORPORATION COMMISSION

2-

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

APR 11 1994  
4-11-94  
CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-077-21,169-0000  
NW NW NW, SECTION 31 TOWNSHIP 31 RANGE 6W

OPERATOR LICENSE # 5429 4950 FEET FROM S SECTION LINE  
4880 FEET FROM E SECTION LINE

OPERATOR BRYCE HAYES  
NAME & P O BOX 108  
ADDRESS ATTICA KS 67009-0108

LEASE NAME: E E KELLER #1  
COUNTY: HARPER

WELL TOTAL DEPTH: 4380' PB-4357' 142.35

PIPE: 4-1/2" @ 4350'

SURFACE CASING: 8-5/8" @ 307'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SUD  DEA

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: CLARKE CORPORATION  
ADDRESS: MEDICINE LODGE KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 28 MONTH: 3 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: BRYCE HAYES  
COMPANY NAME: SAME PHONE: \_\_\_\_\_

WERE: 30 SX ON BTM - 35 SX 1150' - 35 SX 750' - 350' TO  
0'

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: \_\_\_\_\_ DAY: 28 MONTH: 3 YEAR: 1994

ACTUAL PLUGGING REPORT:  
PUMPED 30 SX ON BTM - SHOT 4-1/2" OFF @ 3750' - PULLED  
ALL OF CSG - RAN TUB IN TO 1150' - PUMPED 35 SX -  
PULLED TO 750' - PUMPED 35 SX - PULLED TO 350' - CIRC  
CMT TO SURF

REMARKS: ALLIED CMT #3847 - 60/40 4% GEL

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 4-18-94

INV. NO. 40294

JS/ JACK LUTHI (AGENT)