

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20607-00-00
Spot: NWNE Sec/Twnshp/Rge: 2-31S-7W
660 feet from N Section Line, 660 feet from E Section Line
Lease/Unit Name: OSCAR SMITH Well Number: 1
County: HARPER Total Vertical Depth: 4400 feet

Operator License No.: 6236
Operator Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 238 230 SX CMT
Production: Size 4.5 feet: 4400 125 SX CMT
Liner: Size feet: 143.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/28/2000 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QWS Phone: (316) 532-3794

Proposed Plugging Method: Sand back to 4300' and cap w/5sxs. Recover pipe. 35sxs-1300. 35sxs-850. Circulate cement 300-0.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 11/28/2000 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were covered w/sand to 4300 and capped w/5sxs of cement. The pipe was recovered from 2127 and pulled to 1300' where 35sxs of cement was spotted. The pipe was pulled to 850' where 35sxs of cement was spotted. The pipe was pulled to 300' where cement was circulated to surface. The remaining pipe was pulled and the cement was topped off.

RECEIVED
KCC DISTRICT #2

DEC 01 2000
12-1-00
WICHITA, KS

Remarks: UNITED CEMENTING 60/40 POZ 4% GEL

Plugged through: DP

District: 02

Signed _____ (TECHNICIAN)

INVOICED

DATE 12/7/00
INV. NO. 2001061071