

2 050386

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-01,001-08-01  
SE, SEC. 2, T 31 S, R 7 (W/K)  
330 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corp.  
Name & Address 155 N. Market, Suite 1000  
Wichita, KS 67202

Lease Name Tidwell Well # 1  
County Harper 44.03  
Well Total Depth 4397 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 5:00p.m. Day: 8 Month: 5 Year: 19 86

Plugging proposal received from \_\_\_\_\_

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: 4 1/2" casing set at 4383' with 175 sacks of cement - perf at 4322-4330 -  
sand back to 4177' and dump 4 sacks of cement - shoot and pull pipe

Plugging Proposal Received by \_\_\_\_\_  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30p.m. Day: 13 Month: 5 Year: 19 86

ACTUAL PLUGGING REPORT Sanded back to 4177 feet and dumped 4 sacks of cement. Shot and pulled 3426 feet of 4 1/2" casing. Squeezed 8 5/8" with 15 sacks of gel, 3 sacks of hulls and 75 sacks of 60/40, 4% gel. Closed in 150#

Remarks: 283235 B-J Titan  
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION  
MAY 22 1986  
5-22-86  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE MAY 22 1986

INV. NO. 13944

Signed Glenford Ward  
(TECHNICIAN)  
RD