

15-077-20245-0000

2-040913

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

12-11

API NUMBER: 15-5-13-74

NE/SW/SW, SECTION 24 TOWNSHIP 31 RANGE 6 W

OPERATOR LICENSE # 5259
OPERATOR Mai Oil Operations Inc.
NAME & PO Box 33
ADDRESS Russell KS. 67665
LEASE NAME: Runnymede Unit 1-5

COUNTY: Harper
WELL TOTAL DEPTH: 3930' PBTD 3785'
PIPE: 4 1/2 @ 3930
SURFACE CASING: 8 5/8 @ 260'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Quality Well Service

ADDRESS: Sterling KS. LICENSE:

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: Richard McIntyre

COMPANY NAME: Quality Well Service PHONE:

WERE: Sand to 3460' and 4 sks cement
35 sks @ 1042'
35 sks @ 690'
Circ. Cmt from 306'

RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED BY: Steve VanGieson

JAN 08 1998

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

1-8-98
CONSERVATION DIVISION
WICHITA, KS

COMPLETED: HOUR: 1330 DAY: 11 MONTH: 12 YEAR: 1997

ACTUAL PLUGGING REPORT: The Pers were covered with sand from 3785' to 3460', and capped with 4 sacks of cement. The 4 1/2 was recovered from 3004' and pulled to 1042' where 35 sks. of cement was spotted. The casing was pulled to 690', where 35 sks of cement was spotted. The casing was pulled to 306' where cement was circulated to surface.

REMARKS: Allied Cementing 60/40 Poz 4% gel.

I DID NOT OBSERVE THIS PLUGGING.

STEVE VANGIESON

INVOICED

DATE

INV. NO. 49916