

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2- 040917

12-17

15-077-10043-00-01

API NUMBER: 4-2-57

SW/SE/SW SECTION 24 TOWNSHIP 31 RANGE 6W

OPERATOR LICENSE # 5259

330 FEET FROM S SECTION LINE

OPERATOR Mai Oil Operations

3630 FEET FROM E SECTION LINE

NAME & P O Box 33

ADDRESS Russell Ks. 67665

LEASE NAME: Runnymede 1-2 ^{SPRINGER} 152.56

COUNTY: Harper

WELL TOTAL DEPTH: 4694' PBTD 3900'

PIPE: 7" @4694'

SURFACE CASING: 10 3/4" @ 523'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Quality Well Service

ADDRESS: Sterling Ks. LICENSE: 31925

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: _____

PLUGGING PROPOSAL RECEIVED FROM: Richard McIntyre

COMPANY NAME: Quality Well Service

WERE: Perfs. 3614-3648

Sand to 3560' and 7 sks.

50 sks. @ 1050'

50 sks. @ 700'

Circ. From 201'

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 26 1998
1-26-98

CONSERVATION DIVISION
WICHITA KS

PLUGGING PROPOSAL RECEIVED BY: Steve VanGieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1500 DAY: 17 MONTH: 12 YEAR: 1997

ACTUAL PLUGGING REPORT: The Perfs. Were covered with sand from 3900' to 3512' and capped with 7 sks. Cement. The 7" was recovered from 3006' and pulled to 1050' where 50 sks. Of cement was spotted. The pipe was pulled to 564' where 50 sks. Of cement was spotted. The Pipe was pulled to 201' where cement was circulated to surface. Remaining pipe was pulled and cement topped off.

REMARKS: Allied Cementing 60/40 Poz 4% Gel

I DID OBSERVE THIS PLUGGING.

[Signature]
Steve VanGieson

FORM CP-2/3
REV. 3/90

INVOICED
DATE JAN 28 1998
INV. NO. 49999

12-17 MAR 03 1998