

2 070031

1-29-88

239R

API NUMBER 15-077-00290-00-01

W/2, SEC. 18, T. 31 S, R. 6 XVE

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

Lease Name Schultz Well # B-1

County Harper 156.55

Well Total Depth 4817 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 631

REGISTRATION COMMISSION  
REGISTRATION DIVISION - PLUGGING SECTION  
COLORADO DERBY BUILDING  
PITCHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Operator: Phillips Petroleum Company

Name & Address Route 3, Box 20 A

Great Bend, KS 67530

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Phillips License Number 5229

Address Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 29 Month: 1 Year: 19 88

Plugging proposal received from \_\_\_\_\_

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

Work done: Pump 2 sxs hulls, 50 sxs cement, 30 sxs gel w/siper plug and 65 sxs cement.

Run pipe down back side to 125'. Pump 45 sxs 60/40 4% gel, 3% cc

Plugging Proposal Received by District #2 Office  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00am Day: 29 Month: 1 Year: 1988

ACTUAL PLUGGING REPORT Well was plugged leaving the 5 1/2" in hole. Pumped 2 sxs hulls,

50 sxs cement, 30 sxs gel w/wiper plug and 65 sxs cement. Press. to 1000#.

Shut in at 600#. Ran 3/4" plastic pipe down back side to 125'. Pumped 45 sxs

60/40 4% gel, 3% cc.

Remarks: B. J. Titan

(if additional description is necessary, use BACK of this form.)

INVOICED (if you did not observe this plugging.)

DATE 2-9-88

INV. NO. 19794

Signed Jack R. Schultz  
(TECHNICIAN)

FILED 1988  
2-8-88