

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21184-00-00  
Spot: CN2SE Sec/Twnshp/Rge: 12-31S-8W  
1980 feet from S Section Line, 1320 feet from E Section Line  
Lease/Unit Name: SHORT A Well Number: 1  
County: HARPER Total Vertical Depth: 4820 feet

Operator License No.: 5399  
Operator Name: AMERICAN ENERGIES CORPORA  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.62 feet: 251  
Production: Size 5.5 feet: 4819  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

156.65

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/20/2000  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JOSEPH STRUBE Company: D.S & W SERVICE Phone: (316) 587-3361

Proposed Plugging Method: Sand to 4740 and 5sxs of cement. 35sxs @1300. 35sxs@900. Circulate cement from 300-0.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 09/20/2000 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Sand was dumped over the perms to 4740 and capped w/5sxs of cement. The 5 1/2" was recovered from 2800 feet and pulled to 1330, where 35sxs of cement was spotted in place. The pipe was pulled to 900feet, where 35sx of cement was spotted in place. The was pulled to 300feet, where cement was circulated to surface. The remaining pipe was pulled, and the cement was topped off.

RECEIVED  
KCC DISTRICT #2

OCT 13 2000  
10-13-00  
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 POZ

Plugged through: CSG

District: 02

Signed [Signature]

**INVOICED**

(TECHNICIAN)

DATE 10/23/00

INV. NO. 20010160859