

RECEIVED
STATE CORPORATION COMMISSION

3-7

2-040634

75
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

AUG 4 1991

CONSERVATION DIVISION
Wichita, Kansas

21030-0000

API NUMBER: 15-077-21,300-0

NW SW, SECTION 3 TOWNSHIP 31 RANGE 6W

OPERATOR LICENSE # 6236 1980 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR MTM Petroleum
NAME & Box 82
ADDRESS Spivey, KS 67142

LEASE NAME: Stevens #1

COUNTY: Harper

WELL TOTAL DEPTH: 4380' 142.35

CONDUCTOR PIPE: " @ "

SURFACE CASING: 8-5/8" @ 259'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Val Energy, Inc.
ADDRESS: Box 322, Haysville, KS 67060 LICENSE: 5822

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Todd Allam

COMPANY NAME: Val Energy PHONE: _____
WERE: 5-1/2" @ 4378' - perms 4308'-4378' - sand to 4250' & 6
sx - 35 sx @ 1000 - 35 sx @ 600' - circ 310'.

PLUGGING PROPOSAL RECEIVED BY: Don Thompson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00 DAY: 7 MONTH: 3 YEAR: 1991

ACTUAL PLUGGING REPORT:
Perfs were sanded back to 4250' & capped w/6 sx cmt
thru dump bailer - 5-1/2" was shot loose @ 3207' &
pulled to 1000' where 35 sx cmt spotted - 5-1/2" pulled
to 600' & 35 sx cmt spotted - 5-1/2" pulled to 310' &
cmt circulated to surface.

REMARKS: Allied Cementing 40/60 2% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 8-28-91

INV. NO. 32850

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90

aw