

RECEIVED  
KANSAS CORPORATION COMMISSION

3-22

2-

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

APR 01 1994

4-1-94

CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-077-21,033 - E 25,330  
CO-01

C SW SW , SECTION 3 TOWNSHIP 31 RANGE 6W

OPERATOR LICENSE # 6236  
660 FEET FROM S SECTION LINE  
4620 FEET FROM E SECTION LINE

OPERATOR MTM PETRO INC  
NAME & BOX 82  
ADDRESS SPIVEY KS 67142

LEASE NAME: STEVENS #2 140.79  
COUNTY: HARPER  
WELL TOTAL DEPTH: 2032' 4220' P/B

PIPE:  
SURFACE CASING: 8-5/8" @ 259'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL  SLD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE  
ADDRESS: ATTICA KS LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS

COMPANY NAME: SHAWNEE WELL SERVICE PHONE: \_\_\_\_\_

WERE: 384'-3856' - PBD 4220' - 5-1/2" 4358' - SAND TO  
3447' & 5 SX - 35 SX 850' - 35 SX 550' - CIRC 310'

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 18:15 DAY: 22 MONTH: 3 YEAR: 1994

ACTUAL PLUGGING REPORT:  
PERFS COVERED W/SAND FRM 4220' TO 3747' & CAPPED W/5  
SX CMT - PIPE RECOVERED FROM 3497', PULLED TO 870' & 35  
SX CMT SPOTTED - PIPE PULLED TO 544' & 35 SX CMT  
SPOTTED - PIPE PULLED TO 298' & CMT CIRC TO SURF

REMARKS: ALLIED #2288 60/40 4% GEL

I DID OBSERVE THIS PLUGGING.


1/5  
STEVE VAN GIESON (AGENT)

INVOICED

DATE APR 08 1994

INV. NO. 40276

3-22



**COMPUTER ANALYZED  
LOG SYSTEMS**

COMPANY GENERAL ENERGY DEVELOPERS CORPORATION

WELL STEVEN #2

FIELD \_\_\_\_\_

COUNTY HARPER STATE KANSAS

API NO: \_\_\_\_\_  
LOCATION: \_\_\_\_\_

C - SW - SW

SEC. 03 TWP. 31S RGE. 6W

Elev. 1472' K.B. \_\_\_\_\_

D.F. \_\_\_\_\_

1467' G.L. \_\_\_\_\_

LOGS USED DIGL GD-DSN

Date 9-23-84 Run. No. ONE

Equipment 1891 PRATT

Recorded By G. FOX & S. HASH Witnessed By MR. DILLTS

Part Number 26103

Ticket No \_\_\_\_\_ API Serial No \_\_\_\_\_ PGM Version \_\_\_\_\_

**COMPUTATION PARAMETERS**

ZONE 1	ZONE 2	ZONE 3	ZONE 4	ZONE 5
4332.00	4260.00	3798.00	3034.00	2996.00
4260.00	3798.00	3034.00	2996.00	2900.00
1.000	1.000	1.000	1.000	1.000
2.000	2.000	2.000	1.900	2.000
2.000	2.000	2.000	2.000	2.000
0.036	0.030	0.040	0.040	0.040
0.170	0.170	0.170	0.170	0.170
2.680	2.710	2.710	2.650	2.710
1.000	1.000	1.000	1.000	1.000
55.000	55.000	55.000	55.000	55.000
189.000	189.000	189.000	189.000	189.000
LIME	LIME	LIME	SAND	LIME

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 17 1994  
3-17-94  
CORPORATION DIVISION  
Wichita, Kansas