

RECEIVED  
STATE CORPORATION COMMISSION

8-14

156  
R  
2-040636

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

ATTN: A A 1001  
8-20-91  
CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER: 15-077-20,327-0001 D-18,416

N/2 N/2 SE, SECTION 19 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 6581 2310 FEET FROM S SECTION LINE  
1320 FEET FROM E SECTION LINE

OPERATOR Bison Energy/Attica Gas Ventures  
NAME & 930 E. Central  
ADDRESS Wichita, Kansas 67206

LEASE NAME: Washbon #1  
COUNTY: Harper  
WELL TOTAL DEPTH: 4464' 145.08

CONDUCTOR PIPE: " @ '  
SURFACE CASING: 8-5/8" @ 250'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD D-18,416 D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_  
PLUGGING CONTRACTOR: Shawnee Well Service  
ADDRESS: Attica, KS LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: C. J. Lett  
COMPANY NAME: Bison Energy PHONE: \_\_\_\_\_

WERE: Run 2-3/8" as deep as possible - spot 50 sx common 3%  
cacl - recover csg - spot 35 sx 1600' - spot 35 sx  
1300' - cir @ 300' - PBSD 4440' - disposal perf 3553'-  
3629' - production perf 4410'-4420' - 4-1/2" csg @  
4459' - csg parted @ 3290'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson  
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 14:30 DAY: 14 MONTH: 8 YEAR: 1991

ACTUAL PLUGGING REPORT:  
2-3/8" tub was run in hole to 3290' - slid out window  
- pulled back out to 3200' & spotted 50 sx common, 3%  
cacl on 8/13/91 - TOC in 1-1/2 hours @ 3006 - S.D.F.N.  
- shot csg loose @ 2476' - pulled csg to 1598' &  
spotted 35 sx 40/60 2% gel - pulled csg to 1299' &  
spotted 35 sx 40/60 2% gel - pulled csg to 306' & circ  
cmt to surface.

REMARKS: B. J. Services #648734 40/60 poz 2% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

Steve Van Gieson  
Steve Van Gieson (AGENT)

DATE SEP 06 1991

FORM CP-2/3  
REV. 3/90

INV. NO. 38962

DW

UIC  
FYI  
has transfer  
been filed

# EDMISTON OIL COMPANY, INC.

OIL OPERATORS  
125 N. MARKET, SUITE 1260  
WICHITA, KANSAS 67202-1774

E. K. EDMISTON, *Chairman*  
JON M. CALLEN, *President*

(316) 265-5241

August 8, 1990

VP

West

Mr. Maurice Korphage  
Kansas Corporation Commission  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Re: Washbon #1  
C N/2 SE, Sec 19-31S-8W  
Harper County, Kansas  
Docket No. D-18,416

Dear Mr. Korphage:

Please be advised that Edmiston Oil Co., Inc. no longer operates the above referenced well. The entire interest operated by Edmiston Oil Co., Inc., was sold by the interest owners to:

Attica Gas Venture Corp. #5039  
123 N. Main  
Attica, Kansas 67009  
Contact: P. John Eck

If we can be of further assistance, please don't hesitate to call me.

Sincerely,

Jon M. Callen  
President

JMC/jt

cc: P. John Eck

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1990  
8-14-90  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
KCC DISTRICT #2

AUG 9 1990

WICHITA, KS