

10-26 433

2 040455

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-077-20581-0000

NW NW SW, SEC. 15, T 31 S, R 8 W/EX

2910 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Cramer Well # B-1

Operator: McCoy Petro

County Harper 142.55

Name & Address 110 S. Main Place, #500

Well Total Depth 4386 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8 feet 280

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hayes Well Service License Number _____

Address Attica KS

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Darrah Haason

(company name) McCoy Petro (phone) _____

were: 4-1/2 4375'

CIBP 4310 & 3 sx

Rec. 3310'

Plugging Proposal Received by W.K. (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:30 Day: 26 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT A CIBP was set at 4310' and capped with 3 sx cement - the 4-1/2" casing was shot off and recovered from 3310' - the top was squeezed plugged by pumping 3 sx of hulls, 10 sx of _____, 15 sx of cement, 20 sx of gel, 15 sx of cement - a wiper plug and 8 sx of cement.

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

NOV 9 1988
11-9-88

Remarks: Howco #222453 60/40 poz 2% cc MX 750# SI 600#
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 11-17-88

Signed St. Ashes (TECHNICIAN)

INV. NO. 23003

10-26

DEC 9 1988