

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-28

API NUMBER: 15-077-21047-000G

NW SW SW , SECTION 15 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5003 990 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

OPERATOR McCOY PETROLEUM COMPANY
NAME & 3017 NORTH CYPRUS
ADDRESS WICHITA, KS 67226

LEASE NAME: CRAMER "A" #2
COUNTY: HARPER
WELL TOTAL DEPTH: 4389 142.64
CONDUCTOR PIPE:
SURFACE CASING: 8 5/8" @ 253'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS

COMPANY NAME: SHAWNEE WELL SERVICE PHONE: 316-

WERE: 5 1/2" 4379' CIBP AT 4300' AND 2 SACKS
35 SACKS 1320
35 SACKS 914'
CIRC. CEMENT 316'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART { _____ } NONE { _____ }

COMPLETED: HOUR: 13:00 DAY: 28 MONTH: 2 YEAR: 1996

ACTUAL PLUGGING REPORT:

CIBP SET AT 4300' AND CAPPED WITH 2 SACKS CEMENT. PIPE RECOVERED FROM 2973' AND PULLED TO 1320 WHERE 35 SACKS CEMENT WAS SPOTTED. PIPE PULLED TO 914 WHERE 35 SACKS CEMENT SPOTTED. PIPE PULLED TO 316 WHERE CEMENT WAS CIRC. TO SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: ALLIED CEMENT 60/40 4% GEL.

I DID NOT OBSERVE THIS PLUGGING.

Steve V. Gieson SB
Steve Van Gieson

JUN 27 1996
6-27-96

CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3
REV. 3/90

INVOICED

DATE JUN 28 1996

INV. NO. 44901