

2 100484

2-1

131

API NUMBER 15- 077-21,120 ~~0000~~ R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C N/2 NE NW, SEC. 22, T 31 S, R 6 W&R

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Hufford Well # 1-22

Operator: Murfin Drlg Co.

County Harper 153.56

Name & Address Box 288

Well Total Depth 4725 feet

Russell, KS 67665

Conductor Pipe: Size 4-1/2" feet 4724'

Surface Casing: Size 8-5/8" feet 300'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated perf 4246'-54'

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Bx 347 Chase KS

Company to plug at: Hour: 3:00p Day: 24 Month: 1 Year: 19 89

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling Inc (phone) _____

were: Sand 4200' & dump w/bailer 5 sx - shoot & pull pipe - circulate cement
above & below salt section 1000' & 900' - then 50' below surface at 350' to
surface.

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 4:00p Day: 1 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT Sanded bottom to 4200' & dumped w/bailer 5 sx cement - shot
& pulled 3618' of 4-1/2" to 1000' & circ 30 sx cement - then pulled pipe to
900' & circ 30 sx cement - then pulled pipe to 350' & circ to surface.

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1989
3-24-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____

INVOICED (Additional description is necessary, use BACK of this form.)

DATE 3-30-89

INV. NO. 24303

W L Signed J.C. Sanders
(TECHNICIAN)