

9-28

RECEIVED  
KANSAS CORPORATION COMMISSION

2-040744

DEC 01 1992

12-1-92

CONSERVATION DIVISION  
WICHITA, KS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-077-21,099-0000

SE NE NW, SECTION 11 TOWNSHIP 31 RANGE 6W

OPERATOR LICENSE # 6236 4620 FEET FROM S SECTION LINE  
2970 FEET FROM E SECTION LINE

OPERATOR MTM Petroleum, Inc.  
NAME & ADDRESS 113 Main Street  
Spivey, KS 67142

LEASE NAME: Joslin #1-11  
COUNTY: Harper  
WELL TOTAL DEPTH: 4730' PB 4710'

142.03

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 373'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: VAL Energy  
ADDRESS: Haysville, KS LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Todd Allam

COMPANY NAME: VAL Energy PHONE: \_\_\_\_\_

WERE: 4-1/2 @ 4729' - perfs 4204-4208' - PBD 4710' - chat  
to 4125' & 4 sx - recover pipe - 35 sx @ 950' - 35 sx  
@ 650' - circ cmt 415'

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( \_\_\_\_\_ ) NONE (  )

COMPLETED: HOUR: 11:00 DAY: 28 MONTH: 9 YEAR: 1992

ACTUAL PLUGGING REPORT:

Perfs were covered w/chat to 4125' & capped w/4 sx  
cmt - 4-1/2" recovered from 3000' & pulled to 990' & 35  
sx cmt spotted - pipe pulled to 600' & 35 sx cmt  
spotted - 4-1/2" pulled to 425' & cmt circ to surf.

REMARKS: United Cmt 60/40 4% gel

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE 12-4-92

INV. NO. 36971

/s/

Steve Van Gieson (AGENT)

DW