

2 040151

API NUMBER 15-077-21056-0000 ^R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE-NW, SEC. 15, T 31 S, R 6 ^{WE}
3300 feet from N/S section line
3300 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4121

Lease Name Crane Well # 1

Operator: Kuwanda Resources Inc

County Harper 153.89

Name & Address Box 7265

Well Total Depth 4735 feet

Wichita Ks. 67207

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Brandt Drilling Co License Number 5840

Address Wichita Ks.

Company to plug at: Hour: 1230 Day: 7 Month: 1 Year: 19 85

Plugging proposal received from Jim Moore

(company name) Brandt Drilling Co. (phone) _____

were: 35 SX 950

35 SX 270

25 SX 60

10 SX RH

10 SX MH.

Plugging Proposal Received by Stan (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1545 Day: 7 Month: 1 Year: 19 85

ACTUAL PLUGGING REPORT Fill hole with heavy mud, run drill pipe to 950 and spot 35 sacks of cement. Pull pipe to 270 and spot 35 sacks of cement. Pushed a rubber plug to 60' and fill hole with 25 sacks of cement. Circulate thru drill 10 sacks in the RT hand 10 sacks in the Mouse hole.

Remarks: Sun Cementing 204582
(If additional description is necessary, use BACK of THIS FORM.)

STATE CORPORATION COMMISSION
JAN 14 1985
1-14-85
CONSERVATION DIVISION
WICHITA, KANSAS

I, Stan (did/did not) observe this plugging.

DATE 1-14-85
INV. NO. 6599

Signed Stan (TECHNICIAN)

WK
FEB 18 1985
MAR 18 1985
RO
FORM CP-2/3 Rev. 01-84

MUST BE TYPED

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

State of Kansas
(see rules on reverse side)

Date: 12 5 84
month day year

API Number is 077-21,056-0000

APPLICANT: License # 9121
Name: Kiwanda Resources, Inc.
Address: Box 7265
State/City: Wichita, Kansas 67207
Contact Person: C. Kirk Fraser
Phone: (316) 267-2697
Operator: License # 5840
Name: Brandt Drilling Co., Inc.
State: Wichita, Kansas

C. SE NW Sec 15 Twp 31 S, Rge 6
(location) East West

3300 Ft North from Southeast Corner of Section
3300 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 1980 feet.
County: Harper

Lease Name Crane Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Drilled For: Well Class: Type Equipment:
 Swd Infield Mud Rotary
 Inj Pool Ext. Air Rotary
WO Expl Wildcat Cable

Depth to Bottom of fresh water 80 feet
Lowest usable water formation Harper Sandstone
Depth to Bottom of usable water 200 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 200 feet
Conductor pipe if any required feet
Ground surface elevation N.A. feet MSL

Old well info as follows:
Well Name
Completion Date Old Total Depth
Recorded Total Depth 4700 feet
Recorded Formation at TD Simpson
Producing Formations Mississippi, Simpson

This Authorization Expires 6-3-85
Approved By 12-3-84

Operator will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

1/30/84 Signature of Operator or Agent [Signature] Title

President
MHC/WHO 12/3/84
Form 01-85
Wichita, Kansas

REGULATORY COMMISSION
JAN 14 1985
CONSERVATION DIVISION