

10 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

APR 19 1963
4-19-63
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Socony Mobil Oil Co. Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name Darnes Well No. B # 1

Location SW Sec. 18 Twp. 31 Rge. 8 (E) W

County Harper Total Depth 4470

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:00PM Day 15th Month April Year 1963

The Above well was plugged as follows:

167' of 8 5/8" surface pipe cemented with 150 sacks, 4469' of 5 1/2" long
string. Plugged back to 4439'. Top perferation 4390. Hole was sanded to
4380', cemented with 5 sacks. Pipe was pulled up to 2940' and 75 sacks
of cement pumped in. Pipe was pulled up to 1650' and 75 sacks of cement
was pumped in through 5 1/2" swedge. 100 sacks of cement was pumped in
through 8 5/8" swedge in surface pipe. We let the pipe set over week end,
cement was down to 147' in the surface pipe, hole was filled with mud
to 40', 10' rock bridge, cemented with 10 sacks to base cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/19/63
INV. NO. 6932-u

Signed: Archie Elving
Well Plugging Supervisor