



15-155-20749-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

March 3, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Jim Moore of Brandt Drilling Company has this date requested permission to plug the following described well:

Operator's Full Name: Mur Fin Drilling Company

Complete Address: 617 Union Center, Wichita, Kansas 67202

Lease Name: Benson Well No. 1-19

Location: S/2 S/2 SE Sec. 19 Twp. 25 Rge. 9 (E) (W)

County: Reno Total Depth: 4394'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated: _____

Mr. Moore was instructed to plug the well as follows:

8 3/4" - 310' - 225 sacks Fill hole with mud. Pump 50 sacks
50-50 Puzmix w/ 4% gel and 3% cal. chloride through drill pipe at
400'. Fill hole with mud to 40'. Push plug and 1/2 sack
hulls to 40' and cap hole with 10 sacks cement.
Cement rat hole with 5 sacks cement.

Very truly yours,

MAR 10 1981

CONSERVATION DIVISION
Wichita, Kansas

Arthur J. Larson
Conservation Division Agent