



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 APR 19 1963
 4-19-63
 CONSERVATION DIVISION
 WICHITA, KANSAS

Dear Sir:

Mr. Deacon of Forbes Casing Pulling has this

date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Soony Mobil Oil Co. Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name: Darnes Well No. B # 1

Location: SW Sec. 18 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4470 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Deacon was instructed to plug the well as follows:

4469' of 5 1/2" long string. Plugged back to 4439'. Top
perferation 4390'. 167' of 8 5/8" surface pipe cemented with
150 sacks. Sanded to 4380' cemented with 5 sacks.
Fill hole to 200'. 10' rock bridge, cement with 20 sacks.
Fill hol to 40' with mud, 10' rock bridge, cement with 10
sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent