

R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 077-00299-00-01 (of this well)

Operator's Full Name E K Edmiston

Complete Address 800 Vickers KSB&T Bldg Wichita, KS

Lease Name Washbon Well No. 2-SWD

Location SE/ SW/SE Sec. 19 Twp. 31 Rge. 8 (E) W

County Harper Total Depth 4459

Abandoned Oil Well      Gas Well      Input Well      SWD Well X D & A     

Other well as hereafter indicated     

Plugging Contractor Clarke Corporation

Address 107 W Fowler Medicine Lodge, KS License No. 583

Operation Completed: Hour 10:00 AM Day 18 Month 8 Year 1976

The above well was plugged as follows:

300 ft 8 5/8 surface cement circulated. 1973 ft 5 1/2 long string  
cemented with 175 sacks. Top perf. 1630 ft. Sand to 1610 ft, 5 sacks  
cement with bailer. Pulled 1000 ft 5 1/2. Set 10 ft rock bridge at  
380 ft. Fill hole with 7 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

**INVOICED**

DATE 8/20/76

INV. NO. 3661-W