

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Washborn Well No. # A-1

Location SE SW SE Sec. 19 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4412'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:15PM Day 4th Month August Year 1966

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cemented with 200 sacks. 4412' of 5 1/2" long string, cemented with 150 sacks. Plug back T.D. 4402'. Top perforation 4392'. Bottom of the hole was sanded to 4375', and cemented with 5 sacks. 3310' of 5 1/2" long string was recovered from the hole. Fluid in the hole was bailed down to 240', bridge plug and rock bridge from 240' to 225', and cemented with 35 sacks, bringing the top of the cement to 120', in the surface pipe. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: Ardelia Elving
Well Plugging Supervisor

INVOICED

DATE 8/5/66

INV. NO. 3098-4

AUG 5 1966
8-5-66
CONSERVATION DIVISION
Wichita, Kansas