

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 12 1966  
12-12-66  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Shenandoah Oil Corporation

Complete Address: 406 Mutual Savings Bldg., Fort Worth, Texas

Lease Name Clarence Bornholdt Well No. # 1

Location C NE SW Sec. 7 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4772'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 6:30PM Day 8th Month Dec. Year 1966

The Above well was plugged as follows:

242' of 8 5/8" surface pipe, cement circulated with 300 sacks. Hole  
was filled with drilling mud to 240', 1st cementing plug, bridged with  
2 sacks of dry cement and 1/2 sack of hulls on fluid at 240', and cemented  
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',  
and cemented with 9 sacks to the base of the cellar. Rat and mouse holes  
bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 12/13/66  
INV. NO. 4452-W

Signed: Archie Elving  
Well Plugging Supervisor