

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Woodman & Iannitti Drilling Company  
Complete Address: 706 Union Nat'l. Bk. Bldg., Wichita, Kansas 67202  
Lease Name Dolechek Well No. # 12  
Location NE SE SW Sec. 13 Twp. 16 Rge. 12 (E)    (W) W  
County Barton Total Depth 3330  
Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X  
Other well as hereafter indicated:     
Plugging Contractor: Same ( Co. tools )  
Address: Same License No.     
Operation Completed: Hour 7:45 PM Day 24 Month 5 Year 1968

## The Above well was plugged as follows:

8 5/8" 272' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 40 sax cement thru  
drill pipe. Mud to 260', set plug, & displaced 25 sax cement thru drill pipe.

Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with Sun Cementing

Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Linn  
Well Plugging Supervisor

DATE

5/28/68

INV. NO.

7832-41