

15-077-30085-0000

Form CP-3
Rev. 6-26-62

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1966
12-12-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Jacks Well No. # 1

Location C W/2 SE NE Sec. 2 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4736'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Ks. License No.

Operation Completed: Hour 4:15PM Day 11th Month Dec. Year 1966

The Above well was plugged as follows:

205' of 8 5/8" surface pipe, cement circulated with 170 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 200', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 12/13/66

INV. NO. 4451-u