

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1965
2-8-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name M. H. King Well No. # 3

Location SW SE SE Sec. 18 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4780'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 3:30PM Day 6th Month Feb. Year 1965

The Above well was plugged as follows:

597' of 8 5/8" surface pipe, cemented with 350 sacks. 4780' of 5 1/2" long
string, cemented with 200 sacks. Plug back to 4378'. Top perforation
4354'. Bottom of the hole was sanded to 4340', and cemented with 5 sacks.
3785' of 5 1/2" long string was recovered from the hole. Fluid level in
the hole was now at 300', bridge plug was set on fluid at 300', and 10'
of rock bridge, and cemented with 25 sacks. Hole was filled with mud
to 40', and 10' of rock bridge, and cemented with 10 sacks to the base
of the cellar.

I hereby certify that **INVOICED** the above well was plugged as herein stated.

DATE 2/8/65
INV. NO. 648-41

Signed: Archie Elving
Well Plugging Supervisor