

2 050231

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5447  
Operator: Citites Service Oil & Gas Corp.  
Name & Address 209 E. William  
Wichita, KS 67202

API NUMBER 15- 191-21,727 000  
NWNWNW, SEC. 22, T. 34 S, R 1 W/E  
330 feet from N/X section line  
330 feet from W/E section line  
Lease Name Marlin Mason Well # A-1  
County Sumner 149.50  
Well Total Depth 4600 feet  
Conductor Pipe: Size        feet  
Surface Casing: Size 8 5/8 feet 290 ✓

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D&A       

Other well as hereinafter indicated       

Plugging Contractor Clarke License Number 5105

Address Medicine Lodge, KS

Company to plug at: Hour:        Day: 11 Month: 3 Year: 19 85

Plugging proposal received from       

(company name)        (phone)       

were: plug back 4160'; Perforate at 4130'; sand back 4080' and dump 5 sacks of cement

shot and pull 5 1/2" casing; pump 15 sacks gel, 4 sacks hulls and 115 sacks of cement

Plugging Proposal Received by        (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part        None       

Operations Completed: Hour: 5:00p.m. Day: 12 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Sanded back to 4080' and dumped 5 sacks of cement. Tagged up  
next day at 4000', shot and pulled 2710' of 5 1/2" casing in very good condition. Squeezed  
8 5/8" casing with 15 sacks gel, 3 sacks of hulls and 115 sacks of cement. Maximum PSI 1100

MAR 18 1985

Remarks: Howco Ticket #086608, Calss "A" 3%cc  
(If additional description is necessary, use BACK of this form.)

(I did / did not) observe this plugging.

DATE 3-19-85  
INV. NO. 7389

Signed Glen W. Ward (TECHNICIAN)

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
 (see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: August 15 1984  
 month day year

OPERATOR: License # 5447  
 Name Cities Service Oil & Gas Corp.  
 Address 800 Sutton Place, 209 E. William  
 City/State/Zip Wichita, Kansas 67202  
 Contact Person Daryl Duval  
 Phone 316 265-5624

CONTRACTOR: License # 5146  
 Name Rains & Williamson Oil Co., Inc.  
 City/State 220 W. Douglas, Wichita, KS 67202

| Well Drilled For:                                                    | Well Class:                                 | Type Equipment:                                |
|----------------------------------------------------------------------|---------------------------------------------|------------------------------------------------|
| <input checked="" type="checkbox"/> Oil <input type="checkbox"/> Swd | <input type="checkbox"/> Infill             | <input checked="" type="checkbox"/> Mud Rotary |
| <input type="checkbox"/> Gas <input type="checkbox"/> Inj            | <input type="checkbox"/> Pool Ext.          | <input type="checkbox"/> Air Rotary            |
| <input type="checkbox"/> OWWO <input type="checkbox"/> Expl          | <input checked="" type="checkbox"/> Wildcat | <input type="checkbox"/> Cable                 |

If OWWO: old well info as follows:

Operator \_\_\_\_\_  
 Well Name \_\_\_\_\_  
 Comp Date \_\_\_\_\_ Old Total Depth \_\_\_\_\_  
 Projected Total Depth 4520 \_\_\_\_\_ feet  
 Projected Formation at TD Arbuckle  
 Expected Producing Formations Mississippi, Simpson

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

8-3-84 Signature of Operator or Agent

Daryl Duval

API Number 15-

NW NW NW Sec 22 Twp 34 S. Rge 1 ☐ East ☒ West

(location)

4950

4950

Ft North from Southeast Corner of Section

Ft West from Southeast Corner of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet

County Sumner

Lease Name Marlin Mason "A" Well# 1

Domestic well within 330 feet: ☐ yes ☒ no

Municipal well within one mile: ☐ yes ☒ no

Depth to Bottom of fresh water 60 feet

Lowest usable water formation Wellington

Depth to Bottom of usable water 250 feet

Surface pipe by Alternate: 1 ☒ 2 ☐

Surface pipe to be set 280 feet

Conductor pipe if any required - feet

Ground surface elevation 1156 feet MSL

This Authorization Expires 2/3/85

Approved By 8/3/84

Title Petroleum Engineer

Form C-1 4/84