

NO
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAR 22 1963
3-22-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aylward Drg Co

Complete Address: 813 1st Natl Bk Wichita, Kansas

Lease Name Robinson Well No. 1

Location GNW NW Sec. 2 Twp. 18 Rge. (E) (W) 17

County Rush Total Depth 3588

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Kent Oil Field Service

Address: El Dorado, Kansas License No. 394

Operation Completed: Hour 3~~0~~ 3PM Day 19 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 1083' circulated with cement - 4 1/2" 3588' with 50 sax cement - Perf 3561'.

Pumped 25 sax cement in bottom to kill gas flow - top cement 3250' - pulled 2900' 4 1/2" to 435', circulated hole with heavy gel mud through 4 1/2" (37 sax Gel), displaced 25 sax cement through 4 1/2" at 435', heavy mud to 180', displaced 25 sax cement through 4 1/2" at 180', heavy mud to 25', cement 25' to bottom cellar.

Mudding and cementing by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 3/22/63

Signed: [Signature]
Well Plugging Supervisor

INV. NO. 6463-4