

RECEIVED
STATE CORPORATION COMMISSION

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

NOV 5 1959
11-5-59
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rush

Location: NE SE SW Sec. 3 Twp. 18 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3609

I have this date completed supervision of plugging of:

Lease Name: R~~R~~ Rinehardt Well No. 2

Operator's Full Name: Aylward Drg Co

Complete Address: 813 1st Natl Wichita, Kans

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kans License No. 436

Oil Well _____ Gas Well Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 10 Month 28 Year 59

The above well was plugged as follows:

8 5/8" 1087' circulated with cement - 4 1/2" 3609' with 100 sax cement,
perforated 3585'.

Filled with sand to 3570', set 4 sax cement with dump bailer, pulled 3068'
4 1/2" to 500', circulated hole with heavy mud through 4 1/2" (Gel), displaced
20 sax cement through 4 1/2" at 500', heavy mud to 170', displaced 20 sax
cement through 4 1/2" at 170', heavy mud to 35', set bridge and 10 sax cement
to bottom cellar.

Mudding and cementing by Knight Casing Pulling pump truck.

Signed: *Jewel P. [Signature]*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

INVOICED
DATE 1/11/60
INV. NO. 344-w