

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION
OCT 29 1959
10-29-59
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rush

Location: NE NE SW Sec. 3 Twp. 18 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3606

I have this date completed supervision of plugging of:

Lease Name: Reinhardt Well No. 1

Operator's Full Name: Aylward Drg Co

Complete Address: 813 1st Natl Bk Wichita, Kans

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kans License No. 436

Oil Well _____ Gas Well Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 21 Month 10 Year 59

The above well was plugged as follows:

8 5/8" 1085' circulated with cement - 5 1/2" 3606' with 100 sax cement.

perforations 3564'.

Filled with sand to 3550', set 5 sax cement with dump bailer, pulled 2870'

5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500', displaced

20 sax cement through 5 1/2" at 500', heavy mud to 170', displaced 20 sax

cement through 5 1/2" at 170', heavy mud to 35', set bridge and 10 sax cement

to bottom cellar.

Mudding and cementing by Knight Casing pulling pump truck.

Signed: *Edwin Perry*
Conservation Division Agent

Reviewed: *J. Thomas Buck*
Field Supervisor

Remarks:

INVOICED

DATE 1/12/60
INV. NO. 368-w