

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
11-5-62
NOV 5 1962
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aylward Drg Co
Complete Address: 813 1st Natl Bk Bldg Wichita, Kansas
Lease Name Timken Well No. 1
Location NW SR NE Sec. 3 Twp. 18 Rge. (E) (W) 17
County Rush Total Depth 3663
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: R & D Casing Pulling
Address: Hutchinson, Kansas License No. 236
Operation Completed: Hour 4PM Day 31 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 1072' circulated with 450 sax cement - 4 1/2" 3662' with 125 sax
cement - perforated 3536'.

Filled with sand to 3550', set 4 sax cement with dump bailer - pulled
2600' 4 1/2" to 550', circulated hole with heavy gel mud through 4 1/2" at
550' (21 sax Gel), displaced 20 sax cement through 4 1/2" at 450', heavy
mud to 160', displaced 20 sax cement through 4 1/2" at 160', heavy mud to
35' - cement 35' to bottom cellar.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Peety
Well Plugging Supervisor

DATE 11/7/62
INV. NO. 5960-W