

15-165-20431-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1972
5-22-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Brandt Oil Company
Complete Address Suite 510 300 W Douglas Wichita, Kansas 67202
Lease Name Crotinger Well No. 1
Location 100° W @ N/2 SW SW Sec. 12 Twp. 18 Rge. (E) (W) 17
County Rush Total Depth 3601'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 12 M Day 19 Month 5 Year 1972

The above well was plugged as follows:

Total Depth 3601' 8 5/8 csg set at 1026' cwc 365 sk.
5 1/2 csg set at 3600' cw 75 sk cmt.
Filled 5 1/2 csg W/sd (3585-3601) Dumped 5 sk cmt W/dump bailer. (3550-3585)
Cutoff and recovered 3100' of 5 1/2 csg.
Pumped down 8 5/8 csg with 300 lbs hulls -20 sk gel & water, released 8 5/8 plug and
pumped 120 sk 50-50 poz 2% gel. Pumping pres. 500 lbs. SI pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Wessley
Well Plugging Supervisor

DATE 5/25/72
INV. NO. 5736-W