

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1973
10-29-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Inc.
Complete Address Box 18407 Wichita, Kansas 67218
Lease Name Dinges "B" Well No. 3
Location SE NW NE Sec. 21 Twp. 19 Rge. (E) (W) 25
County Ness Total Depth 4598'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 1 P Day 26 Month 10 Year 1973

The above well was plugged as follows:

Total depth 4598' 8 5/8 csg set at 235' cwc 170 sk.

5 1/2 csg set at 4595' cw 200 sk cmt.

PBTD 4543' with perf. (4330-4335)

Set 5 1/2 plug at 4000' - poured 10' sand - dumped 5 sk cmt W/dump bailer. (3950-4000)

Cutoff and recovered 2650' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls - 70 sk cem. - 10 sk gel & water - released 8 5/8 plug and pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben F. Wasson
Well Plugging Supervisor

DATE 10/30/73

INV. NO. 8084-10