



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 117-42

LOCATION 2406

SEC. 24 TWP. 18 RGE. 16

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Moore

Operator Harwood Oil Co Address 735 Kennedy Bldg - Tulsa Okla

Field _____ County Beck

Total Depth 3565 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 1/2 - 22845 - Connected with 10' sack of cement.
1 3/8 - 756 ft - not connected but 4 ft in hole - 60 sacks of
cement on bottom - hole down for in through the 2" tubing -
Cement to 3460 ft - 8 1/2 x 7" casing killed & pulled out -
Mud from 3460 to 1030 ft - 25 ft of rock bridge - Cement from
1030 ft to 915 ft - Mud from 915 ft to 180 ft - cement from
180 ft to bottom of well - 60 sacks of cement Pumped in between
the 1 1/2 x 1 3/8 casing pipe -

R.S. Pipe Pulling Co
Plugging Contractors

RECEIVED

District Conservation Agent

NOV 23 1949 Date 11-21-49

PLUGGING
FILE SEC. 25 T. 18 R. 16
BOOK PAGE 47 LINE 48

STATE CORPORATION
COMMISSION
KANSAS
11-23-49