

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NEC-NE

SEC. 15 TWP. 18 RGE. 16-00

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease J. H. Nicks

Operator Bushoff Pipe & Supply Co. Address Box # 2301 Tulsa - Okla.

Field _____ County Bush

Total Depth 3566 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10" - 94 ft - 1 1/2" - 336 ft - 1 1/2" - 935 ft -
7" casing set at 3493 ft - 5" casing set at 3519 ft - cemented
Plugged back in the 5" casing to 3490 ft - mixed 5 sacks of
cement at 3490 ft - shot off & pulled the 5" casing -
shot off & pulled 1050 ft of 7" casing - Well showing lots of
salt water - Pumped in 1200 sacks of cement - filling hole
from 1050 ft to the surface with cement -

Pumped in by Kellycutters

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1951

CONSERVATION DIVISION

C. W. [Signature]

District Conservation Agent

Date 10-13-51

PLUGGING
FILE SEC 25 T 18 R 16
BOOK PAGE 70 LINE 16